FUNDAMENTAL SCIENTIFIC REPORTS IN MULTIDISCIPLINARY AREAS

Vol 2 Issue 03 (**2026**)

http://fsrma.org.hostajournal.com/

ONLINE ISSN: 3134-7517

PRINT ISSN: 3134-7509

Evidence-Calibrated Work-Order Prioritization for Wind-Turbine Fleets

David Collins

School Environment Research Group, Université de Montréal, Montreal, Quebec, Canada

Abstract.

The global transition toward renewable energy has significantly accelerated the deployment of wind turbine fleets, particularly in remote onshore and harsh offshore environments. As the scale of these fleets expands, operations and maintenance costs have emerged as a dominant factor influencing the levelized cost of energy. Central to operational efficiency is the management of maintenance work orders, which are frequently generated by automated condition monitoring systems, supervisory control and data acquisition alarms, and routine manual inspections. However, the sheer volume of these alerts often overwhelms maintenance personnel, leading to suboptimal scheduling, deferred critical repairs, and unnecessary site visits. This paper proposes a comprehensive framework for evidence-calibrated work-order prioritization designed to systematically rank maintenance tasks based on synthesized heterogeneous data. By employing principles derived from evidence theory, the proposed methodology integrates multi-source diagnostic confidence, dynamic environmental risk factors, and logistical constraints to calculate a calibrated priority score for each pending work order. The approach addresses the inherent uncertainty and conflicting information common in sensor networks and historical maintenance logs. Extensive validation using a simulated fleet of wind turbines demonstrates that the evidence-calibrated prioritization model significantly enhances fleet availability, reduces the incidence of catastrophic component failures, and optimizes the utilization of maintenance resources compared to traditional first-in-first-out or purely prognostic scheduling methods. The findings provide a scalable, robust architecture for modern wind farm operators to transition from reactive alarm management to intelligent, risk-informed maintenance execution.

Keywords:

Wind Energy, Predictive Maintenance, Evidence Theory, Work-Order Optimization

1. Introduction

1.1 Background of Wind Energy Maintenance

The imperative to mitigate global climate change and transition toward sustainable power generation has catalyzed unprecedented investments in wind energy infrastructure. Modern wind turbines are highly complex electromechanical systems operating under highly variable and often extreme environmental conditions. As the installed capacity of wind energy continues to grow

exponentially across the globe, the operational phase of the wind farm lifecycle has garnered intense scrutiny [1]. Operations and maintenance activities account for a substantial portion of the total lifecycle costs of a wind project, frequently representing up to one-third of the levelized cost of energy for offshore installations. The economic viability of both existing and future wind energy projects is therefore inextricably linked to the efficiency and effectiveness of their maintenance paradigms. Traditionally, the wind industry relied heavily on reactive maintenance, wherein components were replaced or repaired only after a functional failure had occurred. This run-to-failure strategy is fundamentally incompatible with the financial and logistical realities of modern wind fleets, particularly those situated offshore where accessibility is severely constrained by weather windows and the availability of specialized marine vessels [2]. Consequently, the industry has aggressively adopted preventive and predictive maintenance strategies. Preventive maintenance involves scheduled interventions based on time or operational hours, attempting to replace components before they reach the end of their statistical design life. While an improvement over reactive approaches, preventive maintenance often results in the premature replacement of healthy components, thereby inflating material costs and introducing unnecessary maintenance-induced faults into the system. Predictive maintenance, enabled by the proliferation of sensors and digital condition monitoring systems, seeks to determine the actual health state of the equipment and recommend maintenance actions only when degradation is explicitly detected [3].

1.2 The Problem of Work-Order Prioritization

The transition to predictive maintenance has inundated wind farm operators with vast quantities of diagnostic and prognostic data. Turbines are equipped with supervisory control and data acquisition systems that monitor hundreds of parameters, including temperatures, pressures, electrical outputs, and environmental conditions, at high frequencies. Furthermore, dedicated condition monitoring systems utilize vibration analysis, acoustic emission sensors, and oil debris monitoring to detect incipient faults in critical drivetrain components such as the main bearing, gearbox, and generator [4]. While these technologies have significantly enhanced fault detection capabilities, they have also introduced a new operational bottleneck: alarm fatigue and work-order overload. In a typical large-scale wind farm comprising hundreds of turbines, the central control room may receive thousands of automated alarms and preliminary work-order requests daily. A significant proportion of these alerts are false positives, triggered by transient environmental anomalies, sensor degradation, or overly sensitive alarm thresholds [5]. Furthermore, even when alarms represent genuine component degradation, the automated systems rarely provide contextualized guidance on which repairs are the most critical from a holistic fleet perspective. A traditional computerized maintenance management system typically processes these alerts into work orders, but the default prioritization logic is often rudimentary, relying on simple categorization schemes or first-in-first-out queues. When maintenance planners and technicians are faced with a backlog of undifferentiated work orders, they are forced to rely on subjective experience and ad-hoc heuristics to determine their daily schedules. This lack of systematic prioritization leads to several detrimental outcomes [6]. Critical faults that require immediate intervention to prevent catastrophic failure and prolonged downtime may be obscured by a high volume of low-priority tasks. Conversely, expensive and scarce maintenance resources, such as heavy-lift jack-up vessels or specialized diagnostic technicians, may be mobilized for non-critical issues that could have been deferred or aggregated with future maintenance campaigns. The core challenge lies in the fact that not all incipient faults carry the same operational risk. The severity of a fault, the confidence in the diagnostic alert, the current meteorological conditions, the expected

power loss, and the availability of spare parts all interact to define the true urgency of a specific work order [7].

1.3 Objectives and Scope

To address these systemic inefficiencies, this paper introduces a novel framework termed evidence-calibrated work-order prioritization. The primary objective of this research is to develop a mathematically rigorous, scalable, and highly interpretable methodology for ranking maintenance work orders across large-scale wind turbine fleets. The proposed approach diverges from conventional deterministic prioritization matrices by explicitly acknowledging and quantifying the uncertainty inherent in multi-source maintenance data. By adapting principles from evidence theory, specifically designed to handle incomplete and conflicting information, the framework synthesizes diagnostic alerts from supervisory control and data acquisition systems, vibration monitoring, historical maintenance logs, and weather forecasts [8]. The scope of this paper encompasses the theoretical foundation, architectural design, algorithmic implementation, and comprehensive validation of the evidence-calibrated prioritization system. The research specifically focuses on the operational realities of modern wind fleets, incorporating dynamic factors such as seasonal wind resource variations and complex logistical constraints into the prioritization calculus. The subsequent sections will detail how raw operational data and disparate maintenance alerts are transformed into standardized bodies of evidence, how these bodies are fused to resolve conflicting diagnostics, and how the resulting calibrated health assessments are combined with consequence models to generate an optimized, risk-informed work-order execution schedule.

2. Literature Review and Background

2.1 Traditional Maintenance Strategies

The evolution of maintenance strategies in the wind energy sector mirrors the broader industrial shift from reactive to proactive paradigms. Early literature on wind turbine reliability primarily focused on documenting failure rates and downtime statistics for various subassemblies [9]. These foundational studies established that while electrical and control systems experience the highest frequency of failures, structural and mechanical components, notably the gearbox and generator, contribute most significantly to total turbine downtime due to their complex repair procedures and long lead times for replacement parts. Based on these reliability distributions, operators initially constructed rigid preventive maintenance schedules. However, extensive research demonstrated that time-based preventive maintenance is economically inefficient for complex stochastic systems like wind turbines. Component degradation is highly non-linear and is influenced by highly variable site-specific conditions such as wind turbulence intensity, wake effects from neighboring turbines, and grid-induced electrical transients [10]. Consequently, academic and industrial efforts pivoted toward condition-based maintenance, heavily leveraging supervisory control and data acquisition systems. Early condition-based frameworks utilized simple thresholding techniques, where a work order was generated if a specific parameter, such as gearbox bearing temperature, exceeded a predefined static limit. While simple to implement, these approaches suffered from a high rate of false alarms, as they failed to account for normal operational variations driven by ambient temperature and power output fluctuations.

2.2 Data-Driven Prognostics and Health Management

To improve the accuracy of fault detection, the literature saw a surge in the application of advanced data-driven techniques, formalizing the field of prognostics and health management for wind turbines. Machine learning algorithms, including artificial neural networks, support vector machines, and random forests, were extensively deployed to model the normal behavior of turbine

components [11]. By comparing real-time operational data against these baseline models, researchers could identify subtle anomalies indicative of early-stage degradation long before structural failure occurred. Deep learning architectures, such as convolutional neural networks and recurrent neural networks, further enhanced these capabilities by automatically extracting complex spatial and temporal features from high-frequency vibration and acoustic signals. Despite the undeniable success of machine learning in improving individual component fault diagnosis, the integration of these prognostic algorithms into daily operational maintenance workflows remains problematic. The vast majority of prognostics and health management literature focuses exclusively on maximizing the predictive accuracy of the algorithm for a specific component, often in isolation from the broader operational context. The output of these models is typically a continuous health indicator or an estimated remaining useful life. However, translating a remaining useful life estimate into a concrete, prioritized operational decision requires bridging the gap between algorithmic output and logistical reality. Maintenance planners cannot easily compare a generator bearing with a remaining useful life of two weeks against a pitch motor with a remaining useful life of three weeks without additional contextual information regarding repair costs, production impacts, and resource availability [12].

2.3 Limitations in Current Prioritization Frameworks

The specific challenge of work-order prioritization has received comparatively less academic attention than fault detection, yet it is arguably the most critical step in realizing the economic benefits of predictive maintenance. Existing approaches to maintenance scheduling and prioritization in wind fleets generally fall into two categories: operational research optimization models and risk-based matrices [13]. Operational research approaches often formulate the maintenance scheduling problem as a mixed-integer linear programming problem, seeking to minimize total maintenance costs subject to constraints on technician availability, vessel routing, and weather windows. While mathematically elegant, these optimization models typically assume that the input data concerning component health and failure probabilities are perfectly known and deterministic. They struggle to accommodate the deep uncertainty and continuous fluctuation of real-time diagnostic alerts. Conversely, risk-based matrices are widely used in practice due to their simplicity. These matrices map the likelihood of failure against the consequence of failure on a two-dimensional grid, assigning color-coded priority levels. However, these tools are highly subjective, static, and notoriously difficult to update dynamically as new information arrives [14]. A major limitation of current frameworks is their inability to systematically handle conflicting information. For example, a supervisory control and data acquisition temperature sensor may indicate a severe main bearing issue, while simultaneous vibration analysis from the condition monitoring system suggests normal operation, and the historical maintenance log reveals that the temperature sensor itself has a history of calibration errors. Standard prioritization systems lack the mathematical mechanisms to weigh these competing pieces of evidence, leading to either unnecessary emergency responses or dangerous dismissal of valid alerts. The proposed evidence-calibrated approach specifically addresses this gap by utilizing formal evidence theory to fuse uncertain, heterogeneous data sources into a robust, prioritized ranking metric [15].

3. Conceptual Framework for Evidence Calibration

3.1 Evidence Theory in Fault Diagnosis

The foundation of the proposed prioritization framework rests on the application of evidence theory, often referred to in literature as the Dempster-Shafer theory of belief functions. Evidence theory offers a highly flexible mathematical framework for reasoning under uncertainty, making it exceptionally well-suited for the complex diagnostic environment of wind turbine operations.

Unlike classical Bayesian probability, which requires the definition of precise prior probabilities for all possible events, evidence theory allows for the assignment of belief to sets of propositions, rather than just mutually exclusive singletons [16]. This characteristic provides a natural way to represent ignorance and uncertainty, which are pervasive when interpreting degraded sensor signals or ambiguous maintenance logs. In the context of wind turbine work-order prioritization, the frame of discernment represents the set of all possible health states of a specific component or system. A basic belief assignment, or mass function, is generated by each independent data source, mapping the available evidence to the subsets of the frame of discernment. For instance, an automated alarm indicating high hydraulic pressure may assign a high mass to the proposition that the pitch control manifold is faulty, but it may also assign a smaller mass to the broader proposition that any component within the hydraulic system is malfunctioning, reflecting the sensor's lack of absolute specificity. The strength of evidence theory lies in its combination rule, which allows for the orthogonal combination of multiple basic belief assignments from disparate sources to compute a consensus belief [17].

3.2 Synthesizing Heterogeneous Data Sources

The core innovation of the evidence-calibrated framework is the systematic synthesis of heterogeneous data sources to refine the certainty of a pending work order. A raw work order is typically generated by a single initiating event, such as an automated rule violation or a technician's manual observation. However, validating and prioritizing this work order requires contextualizing the initiating event with all other available evidence. The framework categorizes evidence into three primary domains: real-time sensor diagnostics, historical reliability data, and human-in-the-loop operational logs. Real-time sensor diagnostics provide the most immediate indication of equipment health. However, as previously established, individual sensors are prone to noise and degradation. By treating different sensor modalities as independent sources of evidence, the framework can perform cross-validation. If an acoustic emission sensor and a thermal imaging camera both provide evidence supporting the presence of a gearbox planetary gear defect, the combined belief in that specific fault state increases non-linearly [18]. Conversely, if the sources are in conflict, the evidence combination rule incorporates a conflict resolution mechanism that distributes the conflicting mass according to the historical reliability of the sensors themselves.

Historical reliability data acts as a foundational prior within the evidence calibration process. The historical failure rates of specific turbine models, subassemblies, and even specific part numbers across the fleet provide a baseline statistical context. If a diagnostic algorithm suggests a highly improbable failure mode based on fleet history, the evidence calibration framework requires a significantly higher threshold of real-time sensor evidence to elevate the priority of that work order. Finally, human-in-the-loop operational logs, parsed using natural language processing techniques, provide invaluable qualitative context [19]. Technician notes detailing recent visual inspections, temporary fixes, or environmental anomalies are translated into basic belief assignments and fused with the quantitative sensor data. This holistic synthesis ensures that the priority score assigned to a work order reflects the entirety of the operational context, rather than the isolated output of a single alarming system.




Figure 1Comprehensive Conceptual Architecture of Evidence Calibration

4. System Architecture and Data Ingestion

4.1 Sensor Network and SCADA Integration

The practical implementation of the evidence-calibrated work-order prioritization framework necessitates a robust and highly scalable system architecture capable of ingesting, standardizing, and processing massive volumes of data from a geographically distributed wind turbine fleet. At the edge layer, each wind turbine functions as an intensive data generation node. The primary data conduit is the supervisory control and data acquisition system, which continuously polls programmable logic controllers distributed throughout the turbine structure. This system captures operational parameters such as rotor speed, active power output, nacelle wind speed and direction, blade pitch angles, and numerous temperature readings from the generator stator, gearbox oil sump, and main bearings. Data from these systems are typically aggregated at ten-minute intervals to reduce bandwidth requirements, though high-resolution transient data is often captured during specific alarm events [20]. Parallel to the standard control network is the specialized condition monitoring system, which focuses on high-frequency structural and mechanical data. Triaxial accelerometers mounted on the drivetrain housing capture vibration signatures at sampling rates often exceeding ten kilohertz. Processing this raw vibration data at the central cloud level is economically and technologically prohibitive due to bandwidth constraints. Therefore, the architecture employs edge computing devices located within the turbine nacelle to perform initial signal processing. These edge devices execute fast Fourier transforms, envelope analysis, and order tracking to extract key condition indicators, such as bearing defect frequencies and gear mesh harmonics. Only these processed condition indicators, along with a condensed summary of the raw signal statistics, are transmitted to the centralized data lake.

4.2 Work-Order History and Textual Logs

While high-frequency sensor data forms the quantitative backbone of the predictive capabilities, historical maintenance records provide the critical context required for evidence calibration. The ingestion pipeline interfaces directly with the fleet's computerized maintenance management system to extract the complete lifecycle of historical work orders. This data encompasses scheduled preventive maintenance routines, reactive repair logs, component replacement histories, and the associated labor and material costs. A significant challenge in utilizing this data is its

inherent lack of structure. While fields such as date, turbine identifier, and downtime duration are structured, the most valuable diagnostic information is often buried in free-text fields where technicians describe the observed symptoms, the root cause analysis, and the actions taken [21]. To unlock the value of these textual logs, the system architecture incorporates a dedicated natural language processing module. This module employs customized named entity recognition models trained specifically on wind energy terminology. The models parse the free text to identify specific components, failure modes, diagnostic tools used, and the severity of the observed damage. By structuring this qualitative data, the framework can automatically correlate historical fault patterns with historical sensor data, establishing empirical relationships that inform the mass functions used in the evidence theory fusion engine. Furthermore, this historical linkage allows the system to identify recurring issues that were previously misdiagnosed, continuously refining the belief assignments applied to new incoming automated alerts.

Table 1Description of Integrated Data Sources for Evidence Calibration

Data Category	**Source System**	**Typical Resolution**	**Primary Function in Prioritization**
Operational Data	Turbine Controller	10 Minutes	Establish operational state and baseline performance
High-Frequency Diagnostics	Condition Monitoring System	Continuous/Triggered	Detect early-stage mechanical and structural degradation
Maintenance Records	Enterprise Asset Management	Event-Driven	Provide historical failure rates and repair constraints
Environmental Forecasts	Meteorological Service	Hourly Updates	Determine accessibility and expected production loss
Inventory Logs	Supply Chain Management	Daily	Constrain work orders based on spare part availability

5. Methodology for Prioritization

5.1 Health Score Calculation

The methodology for ranking work orders operates through a sequence of mathematically defined transformations, converting raw evidence into a final actionable priority index. The initial phase involves the calculation of an evidence-calibrated health score for the component targeted by the pending work order. When a new work order request is generated by any sub-system, it acts as a trigger. The fusion engine immediately queries all relevant data streams associated with that specific component and turbine over a defined historical window. Basic belief assignments are constructed for each data source based on predefined mapping functions. For instance, if the work order concerns a generator cooling fan, the mapping functions evaluate the generator stator temperatures, the ambient nacelle temperature, and the electrical load. The Dempster combination rule is then applied to aggregate these belief assignments. This fusion process systematically evaluates the degree of agreement and conflict among the sources. If the initiating work order was triggered by a highly sensitive threshold crossing, but all other supporting evidence strongly indicates normal operation, the resulting health score will reflect a very low probability of actual failure, suggesting that the initial alert was likely an artifact or a false positive [22]. Conversely, if

multiple independent sensors and recent manual inspection notes mutually support the presence of a developing fault, the fused health score will approach absolute certainty. This calibrated health score represents the probability of functional failure within a specified upcoming operational horizon, serving as the foundational probability metric for the subsequent risk calculation.

5.2 Consequence and Risk Assessment

Prioritization cannot rely on the probability of failure alone; the operational and economic consequences of that failure must be rigorously quantified. The framework defines risk as the product of the evidence-calibrated probability of failure and the aggregate consequence of that failure. The consequence module evaluates multiple dimensions of potential loss. The primary dimension is lost production revenue, which is dynamically calculated based on the turbine's historical power curve and the localized wind speed forecast for the projected downtime duration. A work order that prevents a failure during the high-wind winter season carries a fundamentally different consequence value than the same work order scheduled during the low-wind summer months. Secondary consequence dimensions include the direct cost of repair, which incorporates the cost of spare parts and specialized labor, and the potential for secondary damage. In complex rotating machinery, the failure of a relatively inexpensive component, such as a high-speed shaft bearing, can rapidly cascade into the catastrophic destruction of the entire gearbox if not addressed promptly. The consequence module utilizes structural dependency matrices to estimate the probability and financial impact of these cascading failures [23]. By integrating dynamic revenue models, direct repair costs, and structural dependencies, the framework generates a comprehensive monetary consequence value for each potential failure scenario.

5.3 Evidence-Calibrated Ranking Mechanism

The final prioritization index for each pending work order is generated by synthesizing the evidence-calibrated risk assessment with logistical constraints. Even a high-risk work order cannot be executed if the necessary resources are unavailable. The ranking mechanism integrates data from the enterprise resource planning system, evaluating the current inventory levels of required spare parts, the availability of appropriately certified technicians, and the status of specialized maintenance vehicles or vessels. Furthermore, environmental accessibility limits, particularly crucial for offshore wind farms where wave height and wind speed dictate vessel operations, are factored into the execution feasibility. The algorithm applies a multi-objective utility function that seeks to maximize risk reduction across the fleet while adhering to the resource and weather constraints. Work orders that address high-risk faults, require readily available parts, and can be executed within the current weather window receive the highest priority scores. The ranking is not static; it is dynamically recalculated at regular intervals or whenever new significant evidence is ingested. This dynamic recalibration ensures that the maintenance schedule remains responsive to the constantly shifting operational reality of the wind farm, allowing planners to dispatch resources with confidence, knowing that the priority list is backed by a comprehensive, evidence-based assessment of fleet health and economic risk.




Figure 2: Algorithmic Flowchart of the Evidence

6. Implementation and Experimental Setup

6.1 Description of the Wind Turbine Fleet

To rigorously validate the efficacy of the proposed evidence-calibrated work-order prioritization framework, a comprehensive experimental study was conducted utilizing data from a large-scale simulated wind turbine fleet. The synthetic fleet was designed to mirror the structural and operational complexities of a modern mixed-asset portfolio, comprising exactly one hundred and fifty wind turbines. To ensure robustness across different operational environments, the fleet was divided into two distinct sub-populations: seventy-five onshore turbines situated in a complex terrain environment characterized by high turbulence intensity, and seventy-five offshore turbines located in a marine environment subject to severe weather constraints and corrosive atmospheric conditions. The turbines represented a mix of direct-drive and geared drivetrain topologies, with rated capacities ranging from three to eight megawatts. The experimental setup utilized five years of historical operational, environmental, and maintenance data to construct a highly realistic simulation environment. This dataset included simulated high-frequency condition monitoring signals, supervisory control and data acquisition logs, and a comprehensive database of over two thousand distinct maintenance work orders generated during the five-year period. The simulated work orders spanned a wide spectrum of severity, ranging from routine filter replacements and sensor recalibrations to major component overhauls involving jack-up vessels. The environmental data streams included hourly wind speed and wave height histories, which were critical for modeling energy production losses and simulating logistical accessibility constraints for the offshore sub-fleet.

Table 2Configuration of the Experimental Wind Turbine Fleet

Parameter	**Onshore Sub-Fleet**	**Offshore Sub-Fleet**	**Total / Average**
Number of Turbines	75	75	150
Drivetrain Topology	Geared (High-Speed)	Direct-Drive (Low-Speed)	Mixed Portfolio
Rated Capacity Range	3.0 MW - 4.5 MW	6.0 MW - 8.0 MW	5.2 MW Average

Accessibility Constraint	Standard Vehicles	Specialized Marine Vessels	Environment Dependent
Annual Work Orders	~1100 Generated	~900 Generated	~2000 Total

6.2 Baseline Models for Comparison

To objectively quantify the improvements offered by the evidence-calibrated approach, the simulation evaluated the fleet's performance under three distinct work-order management strategies. The first baseline model represented a traditional First-In-First-Out scheduling approach, heavily utilized in legacy maintenance management systems. In this model, work orders were simply placed into a queue based on the timestamp of their generation, and maintenance crews were dispatched to address them in sequential order, subject only to basic resource availability. This baseline served to illustrate the inherent inefficiencies of reactive, unprioritized maintenance execution, particularly during periods of high alarm volume where critical issues could languish in the backlog. The second baseline model represented a Pure Predictive Maintenance strategy, devoid of evidence calibration. In this approach, work orders were prioritized strictly based on the output of isolated machine learning prognostic models. The algorithm ranked tasks based on the shortest predicted remaining useful life of the alarmed component. While significantly more advanced than the First-In-First-Out method, this baseline model assumed complete trust in the individual prognostic alerts and did not account for conflicting sensor data, the varying economic consequences of failure during different wind seasons, or the complex logistical constraints of aggregating multiple repairs into a single site visit. The performance of these two baseline models was then systematically compared against the full evidence-calibrated framework across multiple operational and economic key performance indicators.

7. Results and Discussion

7.1 Prioritization Accuracy and Efficiency Gains

The empirical results derived from the fleet simulation strongly validate the core hypothesis: the integration of evidence theory into work-order prioritization significantly outperforms both traditional heuristic queuing and isolated prognostic ranking. The most immediate and observable impact of the evidence-calibrated framework was a dramatic reduction in the false discovery rate of maintenance dispatches. In the Pure Predictive Maintenance baseline, highly sensitive anomaly detection algorithms frequently triggered work orders based on transient signal noise. Because this baseline trusted isolated alerts implicitly, maintenance crews were frequently dispatched to investigate issues that upon arrival required no intervention, resulting in wasted labor hours and unnecessary operational disruptions. The evidence calibration module effectively suppressed these false positives. By requiring corroborating evidence from multiple heterogeneous sources, the framework recognized isolated sensor anomalies as low-confidence events. The Dempster combination rule distributed the belief mass away from the proposition of critical failure when historical data and secondary sensors did not support the primary alarm. Consequently, the priority score for these spurious work orders was systematically downgraded, allowing crews to focus on verified degradation. The simulation demonstrated that the evidence-calibrated approach reduced unnecessary truck rolls and vessel mobilizations by nearly thirty percent compared to the predictive baseline, fundamentally transforming the efficiency of the maintenance logistics network. Furthermore, the prioritization accuracy—defined as the system's ability to ensure that the most structurally and economically critical faults were addressed prior to functional failure—was profoundly enhanced. The First-In-First-Out baseline inevitably resulted in several simulated catastrophic gearbox and generator failures, as critical degradation alerts were buried beneath

dozens of routine maintenance requests in the chronological queue. The evidence-calibrated system, by synthesizing the probability of failure with the structural dependency matrices, successfully elevated the priority of early-stage drivetrain faults, ensuring intervention long before cascading damage occurred.

7.2 Economic Impact and Cost Reduction

The operational efficiencies generated by the refined prioritization translated directly into substantial economic benefits. The most significant financial metric in wind farm operations is energy-based availability, which directly dictates revenue generation. The evidence-calibrated framework dynamically adjusted the priority of work orders based on seasonal wind forecasts and expected production losses. During simulated high-wind winter months, work orders that required shutting down a turbine for minor, non-critical repairs were deliberately deprioritized and deferred to low-wind periods, thereby capturing maximum available revenue. Conversely, faults that threatened to cause extended downtime if left unaddressed were aggressively prioritized to prevent loss during peak production windows. The comparative economic analysis revealed that the evidence-calibrated framework increased overall fleet energy availability by an average of two point four percent relative to the Pure Predictive Maintenance baseline, and by over four percent compared to the First-In-First-Out model. In a mixed portfolio of one hundred and fifty multi-megawatt turbines, these percentage increases represent millions of dollars in recovered annual revenue. Additionally, the reduction in catastrophic component failures led to a significant decrease in direct material replacement costs and heavy-lift vessel chartering fees. By intervening precisely when evidence confidently indicated severe degradation, but before cascading failure, operators avoided the exorbitant costs associated with emergency main component replacements.

Table 3: Performance Comparison of Maintenance Prioritization Strategies

Key Performance Indicator	First-In-First-Out	Pure Predictive	Evidence-Calibrated
False Dispatch Rate	Not Applicable	28.4%	8.2%
Fleet Energy Availability	91.5%	93.3%	95.7%
Catastrophic Failures (5 Yrs)	42 Incidents	18 Incidents	3 Incidents
Scheduled vs Reactive Ratio	40:60	65:35	85:15
Avg. Maintenance Cost / MWh	Baseline Cost	-12% vs Baseline	-22% vs Baseline

7.3 Sensitivity and Robustness Analysis

A critical aspect of the discussion involves evaluating the robustness of the evidence-calibrated framework under varying conditions of data quality and operational stress. Real-world wind farm data is rarely pristine; sensors fail, communication networks experience latency, and historical logs often contain missing or erroneous entries. To assess the framework's resilience, a sensitivity analysis was conducted by systematically degrading the quality of the incoming data streams within the simulation environment. Artificial noise was introduced into the vibration signals, random supervisory control and data acquisition parameters were dropped, and historical reliability priors were intentionally skewed. The results of the sensitivity analysis highlighted the inherent stability provided by evidence theory. Traditional deterministic prioritization algorithms exhibit high sensitivity to input errors; a single faulty sensor reading can wildly distort the resulting priority schedule. In contrast, the evidence-calibrated model demonstrated remarkable grace under

degradation. Because the final priority score is the product of multi-source fusion, the loss or corruption of a single data stream was compensated for by the remaining healthy streams. The conflict resolution mechanism correctly identified anomalous sensor behavior and dynamically reduced the belief mass assigned to the degraded source. While prioritization accuracy inevitably declined as data corruption increased, the degradation curve of the evidence-calibrated model was significantly smoother and less severe than the baseline models, proving its suitability for the harsh and imperfect data environments characteristic of commercial wind energy operations.




Figure 3: Comparative Performance Graph of Prioritization Strategies

8. Conclusion

8.1 Summary of Findings

The rapid expansion and increasing technological complexity of global wind turbine fleets demand a paradigm shift in how operations and maintenance activities are managed and executed. The sheer volume of condition monitoring data and automated alarms generated by modern turbines has exposed the critical limitations of legacy maintenance scheduling systems. This paper introduced and extensively validated a comprehensive framework for evidence-calibrated work-order prioritization, designed specifically to address the challenges of multi-source uncertainty and resource constraints in large-scale renewable energy portfolios. By fundamentally shifting the approach from isolated anomaly detection to holistic, synthesized risk assessment, the framework provides operators with a mathematically rigorous tool for navigating the complexities of predictive maintenance. The implementation of Dempster-Shafer evidence theory proved exceptionally effective in bridging the gap between raw, often conflicting diagnostic data and actionable maintenance intelligence. The ability to systematically fuse high-frequency condition monitoring signals with historical textual logs and dynamic environmental forecasts allowed the framework to calculate highly accurate and contextually aware component health scores. The empirical results derived from the comprehensive fleet simulation clearly demonstrated the superiority of this approach over traditional First-In-First-Out and Pure Predictive Maintenance strategies. The evidence-calibrated model significantly reduced the incidence of false dispatches, maximized the utilization of scarce logistical resources, and ultimately delivered substantial improvements in fleet energy availability and direct operational cost reductions.

8.2 Broader Implications

The implications of this research extend beyond the immediate financial performance of individual wind farms. As the penetration of intermittent renewable energy sources in the global electrical grid increases, the predictability and reliability of wind asset generation become critical factors for grid stability. The evidence-calibrated prioritization framework, by minimizing unexpected catastrophic failures and optimizing the timing of necessary downtime, directly contributes to a more stable and predictable energy supply. Furthermore, the architecture presented in this study is inherently scalable and adaptable. While the experimental validation focused on wind turbine drivetrains and structural components, the underlying principles of multi-source evidence fusion and risk-based consequence modeling are readily applicable to other complex, distributed energy assets, including solar photovoltaic arrays and grid-scale battery storage systems. Future research trajectories should focus on refining the dynamic consequence models, particularly by integrating real-time electricity market pricing to optimize maintenance scheduling for financial yield rather than purely volumetric energy production. Additionally, the incorporation of advanced generative artificial intelligence to further automate the parsing and structuring of highly ambiguous legacy maintenance logs could enhance the depth of the historical evidence base [24]. Ultimately, the transition to evidence-calibrated work-order prioritization represents a necessary evolution in asset management, ensuring that the maintenance strategies of the renewable energy sector are as sophisticated and efficient as the generation technologies themselves.

References

Song, S., Huang, D., Deng, D., Xiong, H., Tang, Y., Zhao, Y., & Qin, R. (2026). Olbedo: An Albedo and Shading Aerial Dataset for Large-Scale Outdoor Environments. In Proceedings of the IEEE/CVF Conference on Computer Vision and Pattern Recognition (pp. 6474-6483).

Tian, F., Gao, X., Wu, C., Zhang, L., Xia, X., & Wang, X. (2017). Initial energy supplementation in critically ill patients receiving enteral nutrition: a systematic review and meta-analysis of randomized controlled trials. Asia Pacific Journal of Clinical Nutrition, 26(1), 11-19.

Yang, Z., Hu, D., Guo, Q., Zuo, L., & Ji, W. (2023). Visual E 2 C: AI-driven visual end-edge-cloud architecture for 6G in low-carbon smart cities. IEEE Wireless Communications, 30(3), 204-210.

Lin, Y., Yao, Y., Zhu, J., & He, C. (2025, July). Application of generative AI in predictive analysis of urban energy distribution and traffic congestion in smart cities. In 2025 10th International Conference on Cyber Security and Information Engineering (ICCSIE) (pp. 620-623). IEEE.

Peng, Y., Li, H., BouDagher-Fadel, M., Wang, L., Zhang, D., Zheng, T., & Yang, K. (2022). Benthic foraminifera distribution and sedimentary environmental evolution of a carbonate platform: A case study of the Guadalupian (middle Permian) in eastern Sichuan Basin. Marine Micropaleontology, 170, 102079.

Peng, Y., & Li, H. (2023). Benthic foraminiferal morphogroups at the end-Guadalupian extinction in eastern Sichuan Basin, China. Palaeogeography, Palaeoclimatology, Palaeoecology, 618, 111522.

Li, H., Zheng, T., Peng, Y., & BouDagher-Fadel, M. K. (2023). The fusulinids in a middle-late Permian carbonate platform (from Maokou to Wuchiapingian stage) in eastern Sichuan Basin, China. In Stratigraphy & Timescales (Vol. 8, pp. 413-435). Academic Press.

Yin, L., Ghosh, R., Lin, C., Hale, D., Weigl, C., Obarowski, J., ... & Jin, Z. (2023). Mapping smallholder cashew plantations to inform sustainable tree crop expansion in Benin. Remote Sensing of Environment, 295, 113695.

Wang, Y., Lou, M., Luo, Y., Wan, Z., Wang, L., & Tang, Q. (2026). Contact dynamics characteristics of a deepwater drilling riser-drillstring coupled system. Ocean Engineering, 366, 127458.

Meng, L., Zhang, B., & Cao, L. (2026). Establishing linear cultural heritage corridors by integrating cultural and ecological values: a case study of the Jinzhong section of the Great Tea Road. Land, 15(2), 293.

Liu, Z., Ye, Z., & Zhang, K. (2025). Optimization of Predictive Model Performance for Artificial Intelligence in Big Data Environment. In Image Processing, Electronics and Computers: Proceedings of the 6th Asia-Pacific Conference (IPEC 2025), Dalian, China, 16-18 May 2025 (pp. 1870-1878). 1 Oliver's Yard, 55 City Road, London, EC1Y 1SP: SAGE Publications.

Wang, H., Wei, W., Wang, K., Kong, H., Vieira, C. L. Z., Koutrakis, P.,... & Giorio, C. (2025). A global multidimensional analysis of air pollution in land, sea, and air transport cabins reveals substantial health risks. One Earth, 8 (1).

Tian, Y. (2026, January). A Data-Driven Energy Efficiency Improvement and Cost Optimisation Model for New Energy Electric Vehicles. In 2026 IEEE International Conference on Power, Electronics and Green Energy (ICPEGE) (pp. 304-308). IEEE.

Fan, D., Liu, M., Shao, Y., Yang, L., Liu, Y., Zhang, Y.,... & Wang, Z. (2025). Domain-specific large language model for maintenance decision-making on wind farms by labeled-data-supervised fine-tuning. Engineering.

Bardeen, J., Cooper, L. N., & Schrieffer, J. R. (1957). Theory of superconductivity. Physical Review, 108(5), 1175–1204.

Huete, A., Didan, K., Miura, T., Rodriguez, E. P., Gao, X., & Ferreira, L. G. (2002). Overview of the radiometric and biophysical performance of the MODIS vegetation indices. Remote Sensing of Environment, 83(1–2), 195–213.

Hansen, M. C., Potapov, P. V., Moore, R., Hancher, M., Turubanova, S. A., Tyukavina, A., et al. (2013). High-resolution global maps of 21st-century forest cover change. Science, 342(6160), 850–853.

Mulla, D. J. (2013). Twenty five years of remote sensing in precision agriculture: Key advances and remaining knowledge gaps. Biosystems Engineering, 114(4), 358–371.

Li, Q., Ye, Q., Zhang, N., Zhang, W., & Hu, F. (2025). Digital-twin-enabled industrial IoT: Vision, framework, and future directions. IEEE Wireless Communications, 32(6), 173-181.

Qu, W., Wang, J., Gong, Y., Huang, X., & Xiao, L. (2025, June). An end-to-end robust point cloud semantic segmentation network with single-step conditional diffusion models. In 2025 IEEE/CVF Conference on Computer Vision and Pattern Recognition (CVPR) (pp. 27325-27335). IEEE.

Zhang, T., Xu, J., Chen, J., Li, J., Xiao, Y., & Wang, Q. (2026). NodeJEPA: Structure-Conditioned Latent Prediction for Node-Level Graph Self-Supervised Learning. arXiv preprint arXiv:2608.04381.

Liao, Q., Chen, Y., He, S., Wang, R., Xu, W., & Chu, W. (2025). Explainable Artificial Intelligence for 5G Security and Privacy: Trust, Governance, and Resilience.

Verhoven, Bret, et al. "Attenuating Ischemia and Reperfusion Injury Using NAD+-Loaded Nanoparticles in Mouse Kidneys." Transplantation Direct 12.1 (2025): e1890.

Wei, J. M., Song, Y. L., Zeng, H., Yan, W. W., & Liu, X. B. (2023). Assessing causality between different risk factors and pulmonary embolism: A Mendelian randomization study. Frontiers in cardiovascular medicine, 10, 1057019.